

Junctions 9	
PICADY 9 - Priority Intersection Module	
Version: 9.5.0.6896 © Copyright TRL Limited, 2018	
For sales and distribution information, program advice and maintenance, contact TRL: +44 (0)1344 379777 software@trl.co.uk www.trlsoftware.co.uk	
The users of this computer program for the solution of an engineering problem are in no way relieved of their responsibility for the correctness of the solution	

Filename: Site 2'.j9

Path: W:\2020\P20-114\junction9 modeling

Report generation date: 09/11/2020 13:38:48

- »Site 2' (Quarry Processing Junction) - Base year, 12hrs
- »Site 2' (Quarry Processing Junction) - Opening year, 12hrs
- »Site 2' (Quarry Processing Junction) - +5, 12hrs
- »Site 2' (Quarry Processing Junction) - +15, 12hrs
- »Site 2' (Quarry Processing Junction) - Opening year+QT, 12hrs
- »Site 2' (Quarry Processing Junction) - +5+QT, 12hrs
- »Site 2' (Quarry Processing Junction) - +15+QT, 12hrs

Summary of junction performance

	12hrs			
	Queue (Veh)	Delay (s)	RFC	LOS
Site 2' (Quarry Processing Junction) - Base year				
Stream B-CD	0.0	0.00	0.00	A
Stream B-AD	0.0	0.00	0.00	A
Stream A-BCD	0.0	0.00	0.00	A
Stream D-AB	0.0	0.00	0.00	A
Stream D-BC	0.0	0.00	0.00	A
Stream C-ABD	0.0	0.00	0.00	A
Site 2' (Quarry Processing Junction) - Opening year				
Stream B-CD	0.0	0.00	0.00	A
Stream B-AD	0.0	0.00	0.00	A
Stream A-BCD	0.0	0.00	0.00	A
Stream D-AB	0.0	0.00	0.00	A
Stream D-BC	0.0	0.00	0.00	A
Stream C-ABD	0.0	0.00	0.00	A
Site 2' (Quarry Processing Junction) - +5				
Stream B-CD	0.0	0.00	0.00	A
Stream B-AD	0.0	0.00	0.00	A
Stream A-BCD	0.0	0.00	0.00	A
Stream D-AB	0.0	0.00	0.00	A
Stream D-BC	0.0	0.00	0.00	A
Stream C-ABD	0.0	0.00	0.00	A
Site 2' (Quarry Processing Junction) - +15				
Stream B-CD	0.0	0.00	0.00	A
Stream B-AD	0.0	0.00	0.00	A
Stream A-BCD	0.0	0.00	0.00	A
Stream D-AB	0.0	0.00	0.00	A
Stream D-BC	0.0	0.00	0.00	A
Stream C-ABD	0.0	0.00	0.00	A
Site 2' (Quarry Processing Junction) - Opening year+QT				
Stream B-CD	0.0	14.44	0.01	B
Stream B-AD	0.0	14.42	0.01	B
Stream A-BCD	0.0	0.00	0.00	A
Stream D-AB	0.0	15.42	0.01	C
Stream D-BC	0.0	15.39	0.01	C
Stream C-ABD	0.0	0.00	0.00	A
Site 2' (Quarry Processing Junction) - +5+QT				
Stream B-CD	0.0	14.46	0.01	B
Stream B-AD	0.0	14.44	0.01	B
Stream A-BCD	0.0	0.00	0.00	A
Stream D-AB	0.0	15.44	0.01	C
Stream D-BC	0.0	15.41	0.01	C
Stream C-ABD	0.0	0.00	0.00	A
Site 2' (Quarry Processing Junction) - +15+QT				
Stream B-CD	0.0	14.48	0.01	B
Stream B-AD	0.0	14.46	0.01	B
Stream A-BCD	0.0	0.00	0.00	A
Stream D-AB	0.0	15.46	0.01	C
Stream D-BC	0.0	15.44	0.01	C
Stream C-ABD	0.0	0.00	0.00	A

Values shown are the highest values encountered over all time segments. Delay is the maximum value of average delay per arriving vehicle.

File summary

File Description

Title	P20-114
Location	Aghamore, Co. Sligo
Site number	2'
Date	02/10/2020
Version	
Status	(new file)
Identifier	
Client	
Jobnumber	
Enumerator	PMCE\papadakisa
Description	

Units

Distance units	Speed units	Traffic units input	Traffic units results	Flow units	Average delay units	Total delay units	Rate of delay units
m	kph	Veh	Veh	perTimeSegment	s	-Min	perMin



The junction diagram reflects the last run of Junctions.

Analysis Options

Vehicle length (m)	Calculate Queue Percentiles	Calculate detailed queueing delay	Calculate residual capacity	RFC Threshold	Average Delay threshold (s)	Queue threshold (PCU)
5.75				0.85	36.00	20.00

Demand Set Summary

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically	Relationship type	Relationship
D1	Base year	12hrs	DIRECT	07:00	19:00	720	60	✓		
D2	Opening year	12hrs	DIRECT	07:00	19:00	720	60	✓		
D3	+5	12hrs	DIRECT	07:00	19:00	720	60	✓		
D4	+15	12hrs	DIRECT	07:00	19:00	720	60	✓		
D5	Quarry Traffic	12hrs	DIRECT	07:00	19:00	720	60			
D6	Opening year+QT	12hrs	DIRECT	07:00	19:00	720	60	✓	Simple	D2+D5
D7	+5+QT	12hrs	DIRECT	07:00	19:00	720	60	✓	Simple	D3+D5
D8	+15+QT	12hrs	DIRECT	07:00	19:00	720	60	✓	Simple	D4+D5

Analysis Set Details

ID	Name	Include in report	Network flow scaling factor (%)	Network capacity scaling factor (%)
A1	Site 2' (Quarry Processing Junction)	✓	100.000	100.000

Site 2' (Quarry Processing Junction) - Base year, 12hrs

Data Errors and Warnings

No errors or warnings

Junction Network

Junctions

Junction	Name	Junction type	Major road direction	Use circulating lanes	Junction Delay (s)	Junction LOS
1	Site 2'	Crossroads	Two-way		0.00	A

Junction Network Options

Driving side	Lighting
Left	Normal/unknown

Arms

Arms

Arm	Name	Description	Arm type
A	L3603 (E)		Major
B	Quarry		Minor
C	L3603 (W)		Major
D	Processing Facility		Minor

Major Arm Geometry

Arm	Width of carriageway (m)	Has kerbed central reserve	Has right turn bay	Visibility for right turn (m)	Blocks?	Blocking queue (PCU)
A - L3603 (E)	6.00			0.0	✓	0.00
C - L3603 (W)	6.00			110.0	✓	0.00

Geometries for Arm C are measured opposite Arm B. Geometries for Arm A (if relevant) are measured opposite Arm D.

Minor Arm Geometry

Arm	Minor arm type	Width at give-way (m)	Width at 5m (m)	Width at 10m (m)	Width at 15m (m)	Width at 20m (m)	Estimate flare length	Flare length (PCU)	Visibility to left (m)	Visibility to right (m)
B - Quarry	One lane plus flare	10.00	6.50	5.00	3.40	3.20	✓	2.00	5	5
D - Processing Facility	One lane plus flare	8.30	4.90	4.40	3.90	3.50	✓	1.00	5	5

Slope / Intercept / Capacity

Priority Intersection Slopes and Intercepts

Junction	Stream	Intercept (Veh/TS)	Slope for A-B	Slope for A-C	Slope for A-D	Slope for B-A	Slope for B-C	Slope for B-D	Slope for C-A	Slope for C-B	Slope for C-D	Slope for D-A	Slope for D-B	Slope for D-C
1	A-D	573.963	-	-	-	-	-	-	0.222	0.318	0.222	-	-	-
1	B-A	509.986	0.093	0.235	0.235	-	-	-	0.148	0.335	-	0.235	0.235	0.117
1	B-C	663.707	0.102	0.257	-	-	-	-	-	-	-	-	-	-
1	B-D, nearside lane	509.986	0.093	0.235	0.235	-	-	-	0.148	0.335	0.148	-	-	-
1	B-D, offside lane	509.986	0.093	0.235	0.235	-	-	-	0.148	0.335	0.148	-	-	-
1	C-B	637.665	0.247	0.247	0.353	-	-	-	-	-	-	-	-	-
1	D-A	622.899	-	-	-	-	-	-	0.241	-	0.095	-	-	-
1	D-B, nearside lane	478.630	0.139	0.139	0.315	-	-	-	0.220	0.220	0.087	-	-	-
1	D-B, offside lane	478.630	0.139	0.139	0.315	-	-	-	0.220	0.220	0.087	-	-	-
1	D-C	478.630	-	0.139	0.315	0.110	0.220	0.220	0.220	0.220	0.087	-	-	-

The slopes and intercepts shown above do NOT include any corrections or adjustments.

Streams may be combined, in which case capacity will be adjusted.

Values are shown for the first time segment only; they may differ for subsequent time segments.

Traffic Demand

Demand Set Details

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically
D1	Base year	12hrs	DIRECT	07:00	19:00	720	60	✓

Vehicle mix varies over time	Vehicle mix varies over turn	Vehicle mix varies over entry	Vehicle mix source	PCU Factor for a HV (PCU)	O-D data varies over time
✓	✓	✓	HV Percentages	2.00	✓

Demand overview (Traffic)

Arm	Linked arm	Profile type	Use O-D data	Scaling Factor (%)
A - L3603 (E)		DIRECT	✓	100.000
B - Quarry		DIRECT	✓	100.000
C - L3603 (W)		DIRECT	✓	100.000
D - Processing Facility		DIRECT	✓	100.000

Origin-Destination Data

Demand (Veh/TS)

07:00 - 08:00

		To			
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	8.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	6.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

08:00 - 09:00

		To			
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	19.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

09:00 - 10:00

		To			
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	14.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

10:00 - 11:00

		To			
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	7.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

11:00 - 12:00

		To			
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	11.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

12:00 - 13:00

		To			
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	9.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	9.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

13:00 - 14:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	17.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	8.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

14:00 - 15:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	11.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

15:00 - 16:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	10.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

16:00 - 17:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	20.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	3.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

17:00 - 18:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	11.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

18:00 - 19:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	7.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	5.00	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Vehicle Mix

Heavy Vehicle Percentages

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	27	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

09:00 - 10:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	17	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	4	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**10:00 - 11:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	13	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**11:00 - 12:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	6	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**12:00 - 13:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	10	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**13:00 - 14:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	13	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**14:00 - 15:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	25	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**15:00 - 16:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	31	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	8	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**16:00 - 17:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	14	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages**17:00 - 18:00**

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	17	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

18:00 - 19:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (Veh)	Max LOS	Average Demand (Veh/TS)	Total Junction Arrivals (Veh)
B-CD	0.00	0.00	0.0	A	0.00	0.00
B-AD	0.00	0.00	0.0	A	0.00	0.00
A-BCD	0.00	0.00	0.0	A	0.00	0.00
A-B					0.00	0.00
A-C					11.75	141.00
D-AB	0.00	0.00	0.0	A	0.00	0.00
D-BC	0.00	0.00	0.0	A	0.00	0.00
C-ABD	0.00	0.00	0.0	A	0.00	0.00
C-D					0.00	0.00
C-A					9.50	114.00

Main Results for each time segment

07:00 - 08:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	574.23	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	507.22	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	572.63	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	8.00	8.00			8.00				
D-AB	0.00	0.00	539.21	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	476.20	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	635.69	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	6.00	6.00			6.00				

08:00 - 09:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.21	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.60	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	551.08	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.00	12.00			12.00				
D-AB	0.00	0.00	535.55	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	472.33	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	633.90	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	19.00	19.00			19.00				

09:00 - 10:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.51	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.09	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	549.95	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.00	10.00			10.00				
D-AB	0.00	0.00	536.90	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.80	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	631.49	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	14.00	14.00			14.00				

10:00 - 11:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.50	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.52	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	553.31	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.00	13.00			13.00				
D-AB	0.00	0.00	538.39	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	475.06	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	632.41	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	7.00	7.00			7.00				

11:00 - 12:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.95	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.68	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	561.68	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.00	11.00			11.00				
D-AB	0.00	0.00	537.63	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.53	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	629.22	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.00	11.00			11.00				

12:00 - 13:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	573.62	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	506.41	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	566.87	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	9.00	9.00			9.00				
D-AB	0.00	0.00	538.22	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	475.20	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	624.78	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	9.00	9.00			9.00				

13:00 - 14:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.27	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.29	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	560.57	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	17.00	17.00			17.00				
D-AB	0.00	0.00	537.75	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.20	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	627.56	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	8.00	8.00			8.00				

14:00 - 15:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	573.01	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.61	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	565.05	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.00	10.00			10.00				
D-AB	0.00	0.00	537.24	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.21	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	613.41	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.00	11.00			11.00				

15:00 - 16:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.86	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.69	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	547.34	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.00	12.00			12.00				
D-AB	0.00	0.00	537.40	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.06	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	616.41	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	10.00	10.00			10.00				

16:00 - 17:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	570.86	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.19	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	551.45	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	20.00	20.00			20.00				
D-AB	0.00	0.00	538.59	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.81	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	623.25	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	3.00	3.00			3.00				

17:00 - 18:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.60	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.27	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	560.02	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.00	12.00			12.00				
D-AB	0.00	0.00	537.27	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.14	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	617.49	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.00	11.00			11.00				

18:00 - 19:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	574.58	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	507.60	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	567.24	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	7.00	7.00			7.00				
D-AB	0.00	0.00	539.53	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	476.56	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	627.19	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	5.00	5.00			5.00				

Site 2' (Quarry Processing Junction) - Opening year, 12hrs

Data Errors and Warnings

No errors or warnings

Junction Network

Junctions

Junction	Name	Junction type	Major road direction	Use circulating lanes	Junction Delay (s)	Junction LOS
1	Site 2'	Crossroads	Two-way		0.00	A

Junction Network Options

Driving side	Lighting
Left	Normal/unknown

Traffic Demand

Demand Set Details

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically
D2	Opening year	12hrs	DIRECT	07:00	19:00	720	60	✓

Vehicle mix varies over time	Vehicle mix varies over turn	Vehicle mix varies over entry	Vehicle mix source	PCU Factor for a HV (PCU)	O-D data varies over time
✓	✓	✓	HV Percentages	2.00	✓

Demand overview (Traffic)

Arm	Linked arm	Profile type	Use O-D data	Scaling Factor (%)
A - L3603 (E)		DIRECT	✓	100.000
B - Quarry		DIRECT	✓	100.000
C - L3603 (W)		DIRECT	✓	100.000
D - Processing Facility		DIRECT	✓	100.000

Origin-Destination Data

07:00 - 08:00

Demand (Veh/TS)

	To				
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0.00	0.00	8.74	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	6.58	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

08:00 - 09:00

Demand (Veh/TS)

	To				
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0.00	0.00	13.25	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	20.65	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

09:00 - 10:00

Demand (Veh/TS)

	To				
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0.00	0.00	11.00	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	15.24	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

10:00 - 11:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.15	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	7.57	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.08	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	11.99	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

11:00 - 12:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	9.83	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	9.92	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

12:00 - 13:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	18.66	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	8.83	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

13:00 - 14:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.82	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	12.08	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

14:00 - 15:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.16	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	10.91	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

15:00 - 16:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	21.91	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	3.25	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

16:00 - 17:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.98	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	12.08	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

17:00 - 18:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	7.57	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	5.41	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

18:00 - 19:00

Vehicle Mix

Heavy Vehicle Percentages

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	28	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	18	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	4	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

10:00 - 11:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	13	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	7	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	10	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	14	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

14:00 - 15:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	26	0	0	0
	D - Processing Facility	0	0	0	0

15:00 - 16:00

Heavy Vehicle Percentages

	To				
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	32	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	9	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

16:00 - 17:00

	To				
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	15	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

17:00 - 18:00

From	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	17	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

18:00 - 19:00

	To				
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (Veh)	Max LOS	Average Demand (Veh/TS)	Total Junction Arrivals (Veh)
B-CD	0.00	0.00	0.0	A	0.00	0.00
B-AD	0.00	0.00	0.0	A	0.00	0.00
A-BCD	0.00	0.00	0.0	A	0.00	0.00
A-B					0.00	0.00
A-C					12.85	154.16
D-AB	0.00	0.00	0.0	A	0.00	0.00
D-BC	0.00	0.00	0.0	A	0.00	0.00
C-ABD	0.00	0.00	0.0	A	0.00	0.00
C-D					0.00	0.00
C-A					10.37	124.50

Main Results for each time segment

07:00 - 08:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	574.00	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	506.96	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	572.50	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	8.74	8.74			8.74				
D-AB	0.00	0.00	539.01	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	475.97	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	635.50	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	6.58	6.58			6.58				

08:00 - 09:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	570.62	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	502.94	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	549.85	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.25	13.25			13.25				
D-AB	0.00	0.00	535.01	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	471.72	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	633.46	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	20.65	20.65			20.65				

09:00 - 10:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.08	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.60	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	548.64	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.00	11.00			11.00				
D-AB	0.00	0.00	536.47	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.33	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	630.96	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	15.24	15.24			15.24				

10:00 - 11:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.11	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.11	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	552.34	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.15	14.15			14.15				
D-AB	0.00	0.00	538.14	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.74	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	631.96	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	7.57	7.57			7.57				

11:00 - 12:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.58	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.26	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	560.99	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.08	12.08			12.08				
D-AB	0.00	0.00	537.28	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.14	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	628.60	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.99	11.99			11.99				

12:00 - 13:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	573.31	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	506.06	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	566.42	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	9.83	9.83			9.83				
D-AB	0.00	0.00	537.90	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.85	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	624.04	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	9.92	9.92			9.92				

13:00 - 14:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	570.69	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.69	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	559.80	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	18.66	18.66			18.66				
D-AB	0.00	0.00	537.38	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.74	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	626.80	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	8.83	8.83			8.83				

14:00 - 15:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.66	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.20	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	564.43	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.82	10.82			10.82				
D-AB	0.00	0.00	536.82	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.78	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	612.35	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.08	12.08			12.08				

15:00 - 16:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.37	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.17	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	546.73	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.16	13.16			13.16				
D-AB	0.00	0.00	537.02	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.61	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	615.26	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	10.91	10.91			10.91				

16:00 - 17:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	570.25	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.60	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	550.60	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	21.91	21.91			21.91				
D-AB	0.00	0.00	538.32	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.43	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	622.28	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	3.25	3.25			3.25				

17:00 - 18:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.23	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.85	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	559.32	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.98	12.98			12.98				
D-AB	0.00	0.00	536.88	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.71	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	616.73	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.08	12.08			12.08				

18:00 - 19:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	574.40	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	507.41	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	566.93	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	7.57	7.57			7.57				
D-AB	0.00	0.00	539.39	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	476.39	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	626.79	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	5.41	5.41			5.41				

Site 2' (Quarry Processing Junction) - +5, 12hrs

Data Errors and Warnings

No errors or warnings

Junction Network

Junctions

Junction	Name	Junction type	Major road direction	Use circulating lanes	Junction Delay (s)	Junction LOS
1	Site 2'	Crossroads	Two-way		0.00	A

Junction Network Options

Driving side	Lighting
Left	Normal/unknown

Traffic Demand

Demand Set Details

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically
D3	+5	12hrs	DIRECT	07:00	19:00	720	60	✓

Vehicle mix varies over time	Vehicle mix varies over turn	Vehicle mix varies over entry	Vehicle mix source	PCU Factor for a HV (PCU)	O-D data varies over time
✓	✓	✓	HV Percentages	2.00	✓

Demand overview (Traffic)

Arm	Linked arm	Profile type	Use O-D data	Scaling Factor (%)
A - L3603 (E)		DIRECT	✓	100.000
B - Quarry		DIRECT	✓	100.000
C - L3603 (W)		DIRECT	✓	100.000
D - Processing Facility		DIRECT	✓	100.000

Origin-Destination Data

Demand (Veh/TS)

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	9.52	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	7.19	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.59	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	22.32	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.06	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	16.50	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

10:00 - 11:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	15.34	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	8.15	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.22	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	13.01	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

11:00 - 12:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.68	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	10.89	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

12:00 - 13:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	20.41	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	9.73	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

13:00 - 14:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.64	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	13.22	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

14:00 - 15:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.38	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	11.85	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

15:00 - 16:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	23.90	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	3.49	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

16:00 - 17:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.97	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	13.22	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

17:00 - 18:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	8.15	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	5.82	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

18:00 - 19:00

Vehicle Mix

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
07:00 - 08:00	From	A - L3603 (E)	0	0	0
		B - Quarry	0	0	0
		C - L3603 (W)	0	0	0
		D - Processing Facility	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
08:00 - 09:00	From	A - L3603 (E)	0	30	0
		B - Quarry	0	0	0
		C - L3603 (W)	0	0	0
		D - Processing Facility	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
09:00 - 10:00	From	A - L3603 (E)	0	19	0
		B - Quarry	0	0	0
		C - L3603 (W)	5	0	0
		D - Processing Facility	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
10:00 - 11:00	From	A - L3603 (E)	0	14	0
		B - Quarry	0	0	0
		C - L3603 (W)	0	0	0
		D - Processing Facility	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
11:00 - 12:00	From	A - L3603 (E)	0	0	0
		B - Quarry	0	0	0
		C - L3603 (W)	7	0	0
		D - Processing Facility	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
12:00 - 13:00	From	A - L3603 (E)	0	0	0
		B - Quarry	0	0	0
		C - L3603 (W)	11	0	0
		D - Processing Facility	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
13:00 - 14:00	From	A - L3603 (E)	0	15	0
		B - Quarry	0	0	0
		C - L3603 (W)	0	0	0
		D - Processing Facility	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
14:00 - 15:00	From	A - L3603 (E)	0	0	0
		B - Quarry	0	0	0
		C - L3603 (W)	27	0	0
		D - Processing Facility	0	0	0

15:00 - 16:00

Heavy Vehicle Percentages

		To			
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	32	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	9	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

		To			
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	16	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

16:00 - 17:00

Heavy Vehicle Percentages

		To			
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	18	0	0	0
	D - Processing Facility	0	0	0	0

17:00 - 18:00

Heavy Vehicle Percentages

		To			
From		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

18:00 - 19:00

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (Veh)	Max LOS	Average Demand (Veh/TS)	Total Junction Arrivals (Veh)
B-CD	0.00	0.00	0.0	A	0.00	0.00
B-AD	0.00	0.00	0.0	A	0.00	0.00
A-BCD	0.00	0.00	0.0	A	0.00	0.00
A-B					0.00	0.00
A-C					13.99	167.86
D-AB	0.00	0.00	0.0	A	0.00	0.00
D-BC	0.00	0.00	0.0	A	0.00	0.00
C-ABD	0.00	0.00	0.0	A	0.00	0.00
C-D					0.00	0.00
C-A					11.28	135.39

Main Results for each time segment

07:00 - 08:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	573.75	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	506.69	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	572.36	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	9.52	9.52			9.52				
D-AB	0.00	0.00	538.80	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	475.73	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	635.31	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	7.19	7.19			7.19				

08:00 - 09:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	569.98	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	502.24	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	548.52	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.59	14.59			14.59				
D-AB	0.00	0.00	534.45	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	471.08	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	632.98	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	22.32	22.32			22.32				

09:00 - 10:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.61	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.08	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	547.22	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.06	12.06			12.06				
D-AB	0.00	0.00	536.03	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	472.84	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	630.37	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	16.50	16.50			16.50				

10:00 - 11:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.70	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.69	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	551.29	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	15.34	15.34			15.34				
D-AB	0.00	0.00	537.88	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.42	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	631.48	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	8.15	8.15			8.15				

11:00 - 12:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.19	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.83	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	560.27	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.22	13.22			13.22				
D-AB	0.00	0.00	536.91	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.73	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	627.93	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	13.01	13.01			13.01				

12:00 - 13:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.99	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.69	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	565.92	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.68	10.68			10.68				
D-AB	0.00	0.00	537.56	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.48	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	623.24	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	10.89	10.89			10.89				

13:00 - 14:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	570.07	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.06	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	558.95	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	20.41	20.41			20.41				
D-AB	0.00	0.00	536.98	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.24	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	625.96	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	9.73	9.73			9.73				

14:00 - 15:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.31	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.77	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	563.74	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.64	11.64			11.64				
D-AB	0.00	0.00	536.38	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.32	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	611.23	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	13.22	13.22			13.22				

15:00 - 16:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	570.86	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.61	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	546.06	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.38	14.38			14.38				
D-AB	0.00	0.00	536.62	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.14	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	614.02	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.85	11.85			11.85				

16:00 - 17:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	569.60	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	502.96	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	549.65	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	23.90	23.90			23.90				
D-AB	0.00	0.00	538.04	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.02	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	621.23	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	3.49	3.49			3.49				

17:00 - 18:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.85	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.41	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	558.55	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.97	13.97			13.97				
D-AB	0.00	0.00	536.47	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.27	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	615.94	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	13.22	13.22			13.22				

18:00 - 19:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	574.22	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	507.21	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	566.60	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	8.15	8.15			8.15				
D-AB	0.00	0.00	539.24	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	476.22	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	626.36	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	5.82	5.82			5.82				

Site 2' (Quarry Processing Junction) - +15, 12hrs

Data Errors and Warnings

No errors or warnings

Junction Network

Junctions

Junction	Name	Junction type	Major road direction	Use circulating lanes	Junction Delay (s)	Junction LOS
1	Site 2'	Crossroads	Two-way		0.00	A

Junction Network Options

Driving side	Lighting
Left	Normal/unknown

Traffic Demand

Demand Set Details

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically
D4	+15	12hrs	DIRECT	07:00	19:00	720	60	✓

Vehicle mix varies over time	Vehicle mix varies over turn	Vehicle mix varies over entry	Vehicle mix source	PCU Factor for a HV (PCU)	O-D data varies over time
✓	✓	✓	HV Percentages	2.00	✓

Demand overview (Traffic)

Arm	Linked arm	Profile type	Use O-D data	Scaling Factor (%)
A - L3603 (E)		DIRECT	✓	100.000
B - Quarry		DIRECT	✓	100.000
C - L3603 (W)		DIRECT	✓	100.000
D - Processing Facility		DIRECT	✓	100.000

Origin-Destination Data

Demand (Veh/TS)

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.32	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	7.84	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	16.07	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	23.99	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.20	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	17.78	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

10:00 - 11:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	16.54	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	8.69	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.44	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	14.05	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

11:00 - 12:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.57	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	11.95	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

12:00 - 13:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	22.28	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	10.71	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

13:00 - 14:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.42	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	14.44	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

14:00 - 15:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	15.68	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	12.81	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

15:00 - 16:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	26.01	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	3.73	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

16:00 - 17:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.91	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	14.44	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

17:00 - 18:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	8.69	0.00
	B - Quarry	0.00	0.00	0.00	0.00
	C - L3603 (W)	6.21	0.00	0.00	0.00
	D - Processing Facility	0.00	0.00	0.00	0.00

18:00 - 19:00

Vehicle Mix

Heavy Vehicle Percentages

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	32	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	20	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	5	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

10:00 - 11:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	14	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	8	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	12	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	16	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

14:00 - 15:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	28	0	0	0
	D - Processing Facility	0	0	0	0

15:00 - 16:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	33	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	10	0	0	0
	D - Processing Facility	0	0	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	17	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

16:00 - 17:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	18	0	0	0
	D - Processing Facility	0	0	0	0

17:00 - 18:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	0	0
	B - Quarry	0	0	0	0
	C - L3603 (W)	0	0	0	0
	D - Processing Facility	0	0	0	0

18:00 - 19:00

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (Veh)	Max LOS	Average Demand (Veh/TS)	Total Junction Arrivals (Veh)
B-CD	0.00	0.00	0.0	A	0.00	0.00
B-AD	0.00	0.00	0.0	A	0.00	0.00
A-BCD	0.00	0.00	0.0	A	0.00	0.00
A-B					0.00	0.00
A-C					15.18	182.12
D-AB	0.00	0.00	0.0	A	0.00	0.00
D-BC	0.00	0.00	0.0	A	0.00	0.00
C-ABD	0.00	0.00	0.0	A	0.00	0.00
C-D					0.00	0.00
C-A					12.22	146.64

Main Results for each time segment

07:00 - 08:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	573.49	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	506.40	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	572.22	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.32	10.32			10.32				
D-AB	0.00	0.00	538.58	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	475.47	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	635.11	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	7.84	7.84			7.84				

08:00 - 09:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	569.27	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	501.47	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	546.95	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	16.07	16.07			16.07				
D-AB	0.00	0.00	533.87	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	470.41	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	632.44	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	23.99	23.99			23.99				

09:00 - 10:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.10	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.51	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	545.49	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.20	13.20			13.20				
D-AB	0.00	0.00	535.57	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	472.32	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	629.67	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	17.78	17.78			17.78				

10:00 - 11:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.29	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.27	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	550.02	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	16.54	16.54			16.54				
D-AB	0.00	0.00	537.62	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.10	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	630.95	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	8.69	8.69			8.69				

11:00 - 12:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.78	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.36	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	559.41	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.44	14.44			14.44				
D-AB	0.00	0.00	536.52	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.30	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	627.12	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	14.05	14.05			14.05				

12:00 - 13:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	572.66	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	505.30	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	565.34	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.57	11.57			11.57				
D-AB	0.00	0.00	537.19	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	474.08	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	622.27	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.95	11.95			11.95				

13:00 - 14:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	569.40	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	502.36	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	557.90	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	22.28	22.28			22.28				
D-AB	0.00	0.00	536.54	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	472.70	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	625.01	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	10.71	10.71			10.71				

14:00 - 15:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.95	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	504.33	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	562.94	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.42	12.42			12.42				
D-AB	0.00	0.00	535.91	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	472.82	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	609.89	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	14.44	14.44			14.44				

15:00 - 16:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	570.30	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.02	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	545.27	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	15.68	15.68			15.68				
D-AB	0.00	0.00	536.20	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	472.65	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	612.54	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.81	12.81			12.81				

16:00 - 17:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	568.88	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	502.27	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	548.42	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	26.01	26.01			26.01				
D-AB	0.00	0.00	537.74	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	473.58	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	620.01	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	3.73	3.73			3.73				

17:00 - 18:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	571.48	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	503.97	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	557.61	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.91	14.91			14.91				
D-AB	0.00	0.00	536.03	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	472.81	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	615.05	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	14.44	14.44			14.44				

18:00 - 19:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.00	0.00	574.04	0.000	0.00	0.0	0.0	0.000	A
B-AD	0.00	0.00	507.03	0.000	0.00	0.0	0.0	0.000	A
A-BCD	0.00	0.00	566.21	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	8.69	8.69			8.69				
D-AB	0.00	0.00	539.10	0.000	0.00	0.0	0.0	0.000	A
D-BC	0.00	0.00	476.06	0.000	0.00	0.0	0.0	0.000	A
C-ABD	0.00	0.00	625.88	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	6.21	6.21			6.21				

Site 2' (Quarry Processing Junction) - Opening year+QT, 12hrs

Data Errors and Warnings

No errors or warnings

Junction Network

Junctions

Junction	Name	Junction type	Major road direction	Use circulating lanes	Junction Delay (s)	Junction LOS
1	Site 2'	Crossroads	Two-way		4.07	A

Junction Network Options

Driving side	Lighting
Left	Normal/unknown

Traffic Demand

Demand Set Details

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically	Relationship type	Relationship
D6	Opening year+QT	12hrs	DIRECT	07:00	19:00	720	60	✓	Simple	D2+D5

Vehicle mix varies over time	Vehicle mix varies over turn	Vehicle mix varies over entry	Vehicle mix source	PCU Factor for a HV (PCU)	O-D data varies over time
✓	✓	✓	HV Percentages	2.00	✓

Demand overview (Traffic)

Arm	Linked arm	Profile type	Use O-D data	Scaling Factor (%)
A - L3603 (E)		DIRECT	✓	100.000
B - Quarry		DIRECT	✓	100.000
C - L3603 (W)		DIRECT	✓	100.000
D - Processing Facility		DIRECT	✓	100.000

Origin-Destination Data

Demand (Veh/TS)

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	9.63	0.00
	B - Quarry	0.00	0.00	0.00	2.73
	C - L3603 (W)	7.06	0.00	0.00	0.00
	D - Processing Facility	0.00	4.71	0.00	0.00

Demand (Veh/TS)

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.19	0.00
	B - Quarry	0.00	0.00	0.00	2.88
	C - L3603 (W)	21.93	0.00	0.00	0.00
	D - Processing Facility	0.00	3.16	0.00	0.00

Demand (Veh/TS)

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.05	0.00
	B - Quarry	0.00	0.00	0.00	3.26
	C - L3603 (W)	15.63	0.00	0.00	0.00
	D - Processing Facility	0.00	3.88	0.00	0.00

10:00 - 11:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	15.02	0.00
	B - Quarry	0.00	0.00	0.00	2.67
	C - L3603 (W)	7.82	0.00	0.00	0.00
	D - Processing Facility	0.00	2.45	0.00	0.00

Demand (Veh/TS)

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.85	0.00
	B - Quarry	0.00	0.00	0.00	2.39
	C - L3603 (W)	12.25	0.00	0.00	0.00
	D - Processing Facility	0.00	2.54	0.00	0.00

Demand (Veh/TS)

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.60	0.00
	B - Quarry	0.00	0.00	0.00	2.39
	C - L3603 (W)	10.11	0.00	0.00	0.00
	D - Processing Facility	0.00	1.89	0.00	0.00

Demand (Veh/TS)

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	19.74	0.00
	B - Quarry	0.00	0.00	0.00	3.32
	C - L3603 (W)	9.15	0.00	0.00	0.00
	D - Processing Facility	0.00	3.10	0.00	0.00

Demand (Veh/TS)

14:00 - 15:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.97	0.00
	B - Quarry	0.00	0.00	0.00	3.53
	C - L3603 (W)	12.43	0.00	0.00	0.00
	D - Processing Facility	0.00	3.44	0.00	0.00

Demand (Veh/TS)

15:00 - 16:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.92	0.00
	B - Quarry	0.00	0.00	0.00	2.33
	C - L3603 (W)	11.19	0.00	0.00	0.00
	D - Processing Facility	0.00	2.76	0.00	0.00

Demand (Veh/TS)

16:00 - 17:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	22.61	0.00
	B - Quarry	0.00	0.00	0.00	2.17
	C - L3603 (W)	3.47	0.00	0.00	0.00
	D - Processing Facility	0.00	2.14	0.00	0.00

Demand (Veh/TS)

17:00 - 18:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.83	0.00
	B - Quarry	0.00	0.00	0.00	2.60
	C - L3603 (W)	12.16	0.00	0.00	0.00
	D - Processing Facility	0.00	0.74	0.00	0.00

18:00 - 19:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.85	0.00
	B - Quarry	0.00	0.00	0.00	0.74
	C - L3603 (W)	5.57	0.00	0.00	0.00
	D - Processing Facility	0.00	1.55	0.00	0.00

Vehicle Mix

Heavy Vehicle Percentages

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	9	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	7	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	33	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	5	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	25	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	7	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

10:00 - 11:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	18	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	6	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	9	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	7	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	12	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	19	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

14:00 - 15:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	10	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	28	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	35	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	11	0	0	0
	D - Processing Facility	0	100	0	0

15:00 - 16:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	18	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	6	0	0	0
	D - Processing Facility	0	100	0	0

16:00 - 17:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	6	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	18	0	0	0
	D - Processing Facility	0	100	0	0

17:00 - 18:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	23	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

18:00 - 19:00

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (Veh)	Max LOS	Average Demand (Veh/TS)	Total Junction Arrivals (Veh)
B-CD	0.01	14.44	0.0	B	1.29	15.50
B-AD	0.01	14.42	0.0	B	1.29	15.50
A-BCD	0.00	0.00	0.0	A	0.00	0.00
A-B					0.00	0.00
A-C					13.94	167.27
D-AB	0.01	15.42	0.0	C	1.35	16.18
D-BC	0.01	15.39	0.0	C	1.35	16.18
C-ABD	0.00	0.00	0.0	A	0.00	0.00
C-D					0.00	0.00
C-A					10.73	128.78

Main Results for each time segment

07:00 - 08:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.36	1.36	252.86	0.005	1.36	0.0	0.0	14.313	B
B-AD	1.36	1.36	253.20	0.005	1.36	0.0	0.0	14.294	B
A-BCD	0.00	0.00	559.42	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	9.63	9.63			9.63				
D-AB	2.36	2.36	237.16	0.010	2.35	0.0	0.0	15.330	C
D-BC	2.36	2.36	237.75	0.010	2.35	0.0	0.0	15.292	C
C-ABD	0.00	0.00	624.38	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	7.06	7.06			7.06				

08:00 - 09:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.44	1.44	250.72	0.006	1.44	0.0	0.0	14.440	B
B-AD	1.44	1.44	251.08	0.006	1.44	0.0	0.0	14.419	B
A-BCD	0.00	0.00	540.28	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.19	14.19			14.19				
D-AB	1.58	1.58	235.08	0.007	1.58	0.0	0.0	15.417	C
D-BC	1.58	1.58	235.48	0.007	1.58	0.0	0.0	15.391	C
C-ABD	0.00	0.00	624.14	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	21.93	21.93			21.93				

09:00 - 10:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.63	1.63	251.58	0.006	1.63	0.0	0.0	14.401	B
B-AD	1.63	1.63	251.99	0.006	1.63	0.0	0.0	14.378	B
A-BCD	0.00	0.00	539.27	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.05	12.05			12.05				
D-AB	1.94	1.94	235.94	0.008	1.94	0.0	0.0	15.384	C
D-BC	1.94	1.94	236.43	0.008	1.94	0.0	0.0	15.351	C
C-ABD	0.00	0.00	624.16	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	15.63	15.63			15.63				

10:00 - 11:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.33	1.33	251.98	0.005	1.33	0.0	0.0	14.362	B
B-AD	1.33	1.33	252.32	0.005	1.33	0.0	0.0	14.342	B
A-BCD	0.00	0.00	544.28	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	15.02	15.02			15.02				
D-AB	1.22	1.22	236.89	0.005	1.23	0.0	0.0	15.278	C
D-BC	1.22	1.22	237.20	0.005	1.23	0.0	0.0	15.255	C
C-ABD	0.00	0.00	625.86	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	7.82	7.82			7.82				

11:00 - 12:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.19	1.19	252.11	0.005	1.19	0.0	0.0	14.346	B
B-AD	1.19	1.19	252.41	0.005	1.19	0.0	0.0	14.329	B
A-BCD	0.00	0.00	552.68	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.85	12.85			12.85				
D-AB	1.27	1.27	236.58	0.005	1.27	0.0	0.0	15.297	C
D-BC	1.27	1.27	236.90	0.005	1.27	0.0	0.0	15.277	C
C-ABD	0.00	0.00	623.88	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.25	12.25			12.25				

12:00 - 13:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.19	1.19	252.52	0.005	1.19	0.0	0.0	14.323	B
B-AD	1.19	1.19	252.82	0.005	1.19	0.0	0.0	14.306	B
A-BCD	0.00	0.00	557.11	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.60	10.60			10.60				
D-AB	0.95	0.95	237.04	0.004	0.95	0.0	0.0	15.250	C
D-BC	0.95	0.95	237.28	0.004	0.95	0.0	0.0	15.235	C
C-ABD	0.00	0.00	620.22	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	10.11	10.11			10.11				

13:00 - 14:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.66	1.66	251.13	0.007	1.66	0.0	0.0	14.429	B
B-AD	1.66	1.66	251.55	0.007	1.66	0.0	0.0	14.405	B
A-BCD	0.00	0.00	551.97	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	19.74	19.74			19.74				
D-AB	1.55	1.55	236.26	0.007	1.55	0.0	0.0	15.337	C
D-BC	1.55	1.55	236.65	0.007	1.55	0.0	0.0	15.311	C
C-ABD	0.00	0.00	621.85	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	9.15	9.15			9.15				

14:00 - 15:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.77	1.77	251.83	0.007	1.77	0.0	0.0	14.395	B
B-AD	1.77	1.77	252.28	0.007	1.77	0.0	0.0	14.369	B
A-BCD	0.00	0.00	553.81	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.97	11.97			11.97				
D-AB	1.72	1.72	236.22	0.007	1.72	0.0	0.0	15.350	C
D-BC	1.72	1.72	236.65	0.007	1.72	0.0	0.0	15.322	C
C-ABD	0.00	0.00	608.16	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.43	12.43			12.43				

15:00 - 16:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.16	1.16	251.57	0.005	1.16	0.0	0.0	14.378	B
B-AD	1.16	1.16	251.86	0.005	1.16	0.0	0.0	14.359	B
A-BCD	0.00	0.00	539.28	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.92	13.92			13.92				
D-AB	1.38	1.38	236.29	0.006	1.38	0.0	0.0	15.327	C
D-BC	1.38	1.38	236.64	0.006	1.38	0.0	0.0	15.304	C
C-ABD	0.00	0.00	611.34	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.19	11.19			11.19				

16:00 - 17:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.09	1.09	251.33	0.004	1.09	0.0	0.0	14.385	B
B-AD	1.09	1.09	251.60	0.004	1.09	0.0	0.0	14.369	B
A-BCD	0.00	0.00	545.06	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	22.61	22.61			22.61				
D-AB	1.07	1.07	236.80	0.005	1.07	0.0	0.0	15.271	C
D-BC	1.07	1.07	237.07	0.005	1.07	0.0	0.0	15.253	C
C-ABD	0.00	0.00	615.32	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	3.47	3.47			3.47				

17:00 - 18:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.30	1.30	251.89	0.005	1.30	0.0	0.0	14.365	B
B-AD	1.30	1.30	252.21	0.005	1.30	0.0	0.0	14.346	B
A-BCD	0.00	0.00	552.33	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.83	13.83			13.83				
D-AB	0.37	0.37	236.63	0.002	0.37	0.0	0.0	15.240	C
D-BC	0.37	0.37	236.72	0.002	0.37	0.0	0.0	15.231	C
C-ABD	0.00	0.00	612.69	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.16	12.16			12.16				

18:00 - 19:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.37	0.37	252.91	0.001	0.38	0.0	0.0	14.257	B
B-AD	0.37	0.37	253.01	0.001	0.38	0.0	0.0	14.252	B
A-BCD	0.00	0.00	547.91	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.86	10.86			10.86				
D-AB	0.78	0.78	237.57	0.003	0.77	0.0	0.0	15.202	C
D-BC	0.78	0.78	237.76	0.003	0.77	0.0	0.0	15.189	C
C-ABD	0.00	0.00	621.33	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	5.57	5.57			5.57				

Site 2' (Quarry Processing Junction) - +5+QT, 12hrs

Data Errors and Warnings

No errors or warnings

Junction Network

Junctions

Junction	Name	Junction type	Major road direction	Use circulating lanes	Junction Delay (s)	Junction LOS
1	Site 2'	Crossroads	Two-way		3.84	A

Junction Network Options

Driving side	Lighting
Left	Normal/unknown

Traffic Demand

Demand Set Details

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically	Relationship type	Relationship
D7	+5+QT	12hrs	DIRECT	07:00	19:00	720	60	✓	Simple	D3+D5

Vehicle mix varies over time	Vehicle mix varies over turn	Vehicle mix varies over entry	Vehicle mix source	PCU Factor for a HV (PCU)	O-D data varies over time
✓	✓	✓	HV Percentages	2.00	✓

Demand overview (Traffic)

Arm	Linked arm	Profile type	Use O-D data	Scaling Factor (%)
A - L3603 (E)		DIRECT	✓	100.000
B - Quarry		DIRECT	✓	100.000
C - L3603 (W)		DIRECT	✓	100.000
D - Processing Facility		DIRECT	✓	100.000

Origin-Destination Data

Demand (Veh/TS)

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	10.41	0.00
	B - Quarry	0.00	0.00	0.00	2.73
	C - L3603 (W)	7.68	0.00	0.00	0.00
	D - Processing Facility	0.00	4.71	0.00	0.00

Demand (Veh/TS)

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	15.53	0.00
	B - Quarry	0.00	0.00	0.00	2.88
	C - L3603 (W)	23.61	0.00	0.00	0.00
	D - Processing Facility	0.00	3.16	0.00	0.00

Demand (Veh/TS)

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.11	0.00
	B - Quarry	0.00	0.00	0.00	3.26
	C - L3603 (W)	16.90	0.00	0.00	0.00
	D - Processing Facility	0.00	3.88	0.00	0.00

10:00 - 11:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	16.20	0.00
	B - Quarry	0.00	0.00	0.00	2.67
	C - L3603 (W)	8.40	0.00	0.00	0.00
	D - Processing Facility	0.00	2.45	0.00	0.00

Demand (Veh/TS)

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.00	0.00
	B - Quarry	0.00	0.00	0.00	2.39
	C - L3603 (W)	13.27	0.00	0.00	0.00
	D - Processing Facility	0.00	2.54	0.00	0.00

Demand (Veh/TS)

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.46	0.00
	B - Quarry	0.00	0.00	0.00	2.39
	C - L3603 (W)	11.09	0.00	0.00	0.00
	D - Processing Facility	0.00	1.89	0.00	0.00

Demand (Veh/TS)

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	21.49	0.00
	B - Quarry	0.00	0.00	0.00	3.32
	C - L3603 (W)	10.05	0.00	0.00	0.00
	D - Processing Facility	0.00	3.10	0.00	0.00

Demand (Veh/TS)

14:00 - 15:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.79	0.00
	B - Quarry	0.00	0.00	0.00	3.53
	C - L3603 (W)	13.57	0.00	0.00	0.00
	D - Processing Facility	0.00	3.44	0.00	0.00

Demand (Veh/TS)

15:00 - 16:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	15.14	0.00
	B - Quarry	0.00	0.00	0.00	2.33
	C - L3603 (W)	12.13	0.00	0.00	0.00
	D - Processing Facility	0.00	2.76	0.00	0.00

Demand (Veh/TS)

16:00 - 17:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	24.61	0.00
	B - Quarry	0.00	0.00	0.00	2.17
	C - L3603 (W)	3.71	0.00	0.00	0.00
	D - Processing Facility	0.00	2.14	0.00	0.00

Demand (Veh/TS)

17:00 - 18:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.81	0.00
	B - Quarry	0.00	0.00	0.00	2.60
	C - L3603 (W)	13.30	0.00	0.00	0.00
	D - Processing Facility	0.00	0.74	0.00	0.00

18:00 - 19:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.43	0.00
	B - Quarry	0.00	0.00	0.00	0.74
	C - L3603 (W)	5.98	0.00	0.00	0.00
	D - Processing Facility	0.00	1.55	0.00	0.00

Vehicle Mix

Heavy Vehicle Percentages

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	9	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	6	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	34	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	4	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	25	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	7	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

10:00 - 11:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	18	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	6	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	9	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	7	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	13	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	19	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

14:00 - 15:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	9	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	29	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	35	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	11	0	0	0
	D - Processing Facility	0	100	0	0

15:00 - 16:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	18	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	6	0	0	0
	D - Processing Facility	0	100	0	0

16:00 - 17:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	6	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	18	0	0	0
	D - Processing Facility	0	100	0	0

17:00 - 18:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	22	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

18:00 - 19:00

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (Veh)	Max LOS	Average Demand (Veh/TS)	Total Junction Arrivals (Veh)
B-CD	0.01	14.46	0.0	B	1.29	15.50
B-AD	0.01	14.44	0.0	B	1.29	15.50
A-BCD	0.00	0.00	0.0	A	0.00	0.00
A-B					0.00	0.00
A-C					15.08	180.97
D-AB	0.01	15.44	0.0	C	1.35	16.18
D-BC	0.01	15.41	0.0	C	1.35	16.18
C-ABD	0.00	0.00	0.0	A	0.00	0.00
C-D					0.00	0.00
C-A					11.64	139.67

Main Results for each time segment

07:00 - 08:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.36	1.36	252.72	0.005	1.36	0.0	0.0	14.321	B
B-AD	1.36	1.36	253.06	0.005	1.36	0.0	0.0	14.301	B
A-BCD	0.00	0.00	560.22	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	10.41	10.41			10.41				
D-AB	2.36	2.36	237.04	0.010	2.35	0.0	0.0	15.338	C
D-BC	2.36	2.36	237.63	0.010	2.35	0.0	0.0	15.300	C
C-ABD	0.00	0.00	625.04	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	7.68	7.68			7.68				

08:00 - 09:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.44	1.44	250.37	0.006	1.44	0.0	0.0	14.461	B
B-AD	1.44	1.44	250.73	0.006	1.44	0.0	0.0	14.440	B
A-BCD	0.00	0.00	539.75	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	15.53	15.53			15.53				
D-AB	1.58	1.58	234.76	0.007	1.58	0.0	0.0	15.440	C
D-BC	1.58	1.58	235.16	0.007	1.58	0.0	0.0	15.413	C
C-ABD	0.00	0.00	624.34	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	23.61	23.61			23.61				

09:00 - 10:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.63	1.63	251.32	0.006	1.63	0.0	0.0	14.416	B
B-AD	1.63	1.63	251.73	0.006	1.63	0.0	0.0	14.393	B
A-BCD	0.00	0.00	538.68	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.11	13.11			13.11				
D-AB	1.94	1.94	235.70	0.008	1.94	0.0	0.0	15.400	C
D-BC	1.94	1.94	236.18	0.008	1.94	0.0	0.0	15.368	C
C-ABD	0.00	0.00	624.05	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	16.90	16.90			16.90				

10:00 - 11:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.33	1.33	251.77	0.005	1.33	0.0	0.0	14.376	B
B-AD	1.33	1.33	252.11	0.005	1.33	0.0	0.0	14.354	B
A-BCD	0.00	0.00	543.92	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	16.20	16.20			16.20				
D-AB	1.22	1.22	236.73	0.005	1.23	0.0	0.0	15.288	C
D-BC	1.22	1.22	237.03	0.005	1.23	0.0	0.0	15.265	C
C-ABD	0.00	0.00	625.80	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	8.40	8.40			8.40				

11:00 - 12:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.19	1.19	251.89	0.005	1.19	0.0	0.0	14.359	B
B-AD	1.19	1.19	252.19	0.005	1.19	0.0	0.0	14.344	B
A-BCD	0.00	0.00	552.63	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.00	14.00			14.00				
D-AB	1.27	1.27	236.38	0.005	1.27	0.0	0.0	15.311	C
D-BC	1.27	1.27	236.70	0.005	1.27	0.0	0.0	15.290	C
C-ABD	0.00	0.00	623.54	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	13.27	13.27			13.27				

12:00 - 13:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.19	1.19	252.34	0.005	1.19	0.0	0.0	14.333	B
B-AD	1.19	1.19	252.64	0.005	1.19	0.0	0.0	14.316	B
A-BCD	0.00	0.00	557.34	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.46	11.46			11.46				
D-AB	0.95	0.95	236.85	0.004	0.95	0.0	0.0	15.262	C
D-BC	0.95	0.95	237.09	0.004	0.95	0.0	0.0	15.246	C
C-ABD	0.00	0.00	619.71	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.09	11.09			11.09				

13:00 - 14:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.66	1.66	250.81	0.007	1.66	0.0	0.0	14.447	B
B-AD	1.66	1.66	251.23	0.007	1.66	0.0	0.0	14.423	B
A-BCD	0.00	0.00	551.77	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	21.49	21.49			21.49				
D-AB	1.55	1.55	236.01	0.007	1.55	0.0	0.0	15.353	C
D-BC	1.55	1.55	236.40	0.007	1.55	0.0	0.0	15.327	C
C-ABD	0.00	0.00	621.40	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	10.05	10.05			10.05				

14:00 - 15:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.77	1.77	251.62	0.007	1.77	0.0	0.0	14.407	B
B-AD	1.77	1.77	252.06	0.007	1.77	0.0	0.0	14.381	B
A-BCD	0.00	0.00	553.88	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.79	12.79			12.79				
D-AB	1.72	1.72	235.99	0.007	1.72	0.0	0.0	15.366	C
D-BC	1.72	1.72	236.42	0.007	1.72	0.0	0.0	15.337	C
C-ABD	0.00	0.00	607.38	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	13.57	13.57			13.57				

15:00 - 16:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.16	1.16	251.30	0.005	1.16	0.0	0.0	14.391	B
B-AD	1.16	1.16	251.59	0.005	1.16	0.0	0.0	14.374	B
A-BCD	0.00	0.00	539.18	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	15.14	15.14			15.14				
D-AB	1.38	1.38	236.06	0.006	1.38	0.0	0.0	15.342	C
D-BC	1.38	1.38	236.40	0.006	1.38	0.0	0.0	15.319	C
C-ABD	0.00	0.00	610.42	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.13	12.13			12.13				

16:00 - 17:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.09	1.09	251.01	0.004	1.09	0.0	0.0	14.403	B
B-AD	1.09	1.09	251.28	0.004	1.09	0.0	0.0	14.390	B
A-BCD	0.00	0.00	544.56	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	24.61	24.61			24.61				
D-AB	1.07	1.07	236.59	0.005	1.07	0.0	0.0	15.287	C
D-BC	1.07	1.07	236.86	0.005	1.07	0.0	0.0	15.266	C
C-ABD	0.00	0.00	614.76	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	3.71	3.71			3.71				

17:00 - 18:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.30	1.30	251.67	0.005	1.30	0.0	0.0	14.377	B
B-AD	1.30	1.30	252.00	0.005	1.30	0.0	0.0	14.359	B
A-BCD	0.00	0.00	552.07	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.81	14.81			14.81				
D-AB	0.37	0.37	236.41	0.002	0.37	0.0	0.0	15.254	C
D-BC	0.37	0.37	236.50	0.002	0.37	0.0	0.0	15.245	C
C-ABD	0.00	0.00	612.17	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	13.30	13.30			13.30				

18:00 - 19:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.37	0.37	252.81	0.001	0.38	0.0	0.0	14.263	B
B-AD	0.37	0.37	252.91	0.001	0.38	0.0	0.0	14.257	B
A-BCD	0.00	0.00	548.59	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.43	11.43			11.43				
D-AB	0.78	0.78	237.48	0.003	0.77	0.0	0.0	15.207	C
D-BC	0.78	0.78	237.67	0.003	0.77	0.0	0.0	15.195	C
C-ABD	0.00	0.00	621.20	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	5.98	5.98			5.98				

Site 2' (Quarry Processing Junction) - +15+QT, 12hrs

Data Errors and Warnings

No errors or warnings

Junction Network

Junctions

Junction	Name	Junction type	Major road direction	Use circulating lanes	Junction Delay (s)	Junction LOS
1	Site 2'	Crossroads	Two-way		3.62	A

Junction Network Options

Driving side	Lighting
Left	Normal/unknown

Traffic Demand

Demand Set Details

ID	Scenario name	Time Period name	Traffic profile type	Start time (HH:mm)	Finish time (HH:mm)	Time period length (min)	Time segment length (min)	Run automatically	Relationship type	Relationship
D8	+15+QT	12hrs	DIRECT	07:00	19:00	720	60	✓	Simple	D4+D5

Vehicle mix varies over time	Vehicle mix varies over turn	Vehicle mix varies over entry	Vehicle mix source	PCU Factor for a HV (PCU)	O-D data varies over time
✓	✓	✓	HV Percentages	2.00	✓

Demand overview (Traffic)

Arm	Linked arm	Profile type	Use O-D data	Scaling Factor (%)
A - L3603 (E)		DIRECT	✓	100.000
B - Quarry		DIRECT	✓	100.000
C - L3603 (W)		DIRECT	✓	100.000
D - Processing Facility		DIRECT	✓	100.000

Origin-Destination Data

Demand (Veh/TS)

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.21	0.00
	B - Quarry	0.00	0.00	0.00	2.73
	C - L3603 (W)	8.32	0.00	0.00	0.00
	D - Processing Facility	0.00	4.71	0.00	0.00

Demand (Veh/TS)

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	17.01	0.00
	B - Quarry	0.00	0.00	0.00	2.88
	C - L3603 (W)	25.27	0.00	0.00	0.00
	D - Processing Facility	0.00	3.16	0.00	0.00

Demand (Veh/TS)

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	14.25	0.00
	B - Quarry	0.00	0.00	0.00	3.26
	C - L3603 (W)	18.17	0.00	0.00	0.00
	D - Processing Facility	0.00	3.88	0.00	0.00

10:00 - 11:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	17.40	0.00
	B - Quarry	0.00	0.00	0.00	2.67
	C - L3603 (W)	8.95	0.00	0.00	0.00
	D - Processing Facility	0.00	2.45	0.00	0.00

Demand (Veh/TS)

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	15.21	0.00
	B - Quarry	0.00	0.00	0.00	2.39
	C - L3603 (W)	14.31	0.00	0.00	0.00
	D - Processing Facility	0.00	2.54	0.00	0.00

Demand (Veh/TS)

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	12.34	0.00
	B - Quarry	0.00	0.00	0.00	2.39
	C - L3603 (W)	12.15	0.00	0.00	0.00
	D - Processing Facility	0.00	1.89	0.00	0.00

Demand (Veh/TS)

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	23.36	0.00
	B - Quarry	0.00	0.00	0.00	3.32
	C - L3603 (W)	11.03	0.00	0.00	0.00
	D - Processing Facility	0.00	3.10	0.00	0.00

Demand (Veh/TS)

14:00 - 15:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	13.57	0.00
	B - Quarry	0.00	0.00	0.00	3.53
	C - L3603 (W)	14.79	0.00	0.00	0.00
	D - Processing Facility	0.00	3.44	0.00	0.00

Demand (Veh/TS)

15:00 - 16:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	16.44	0.00
	B - Quarry	0.00	0.00	0.00	2.33
	C - L3603 (W)	13.09	0.00	0.00	0.00
	D - Processing Facility	0.00	2.76	0.00	0.00

Demand (Veh/TS)

16:00 - 17:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	26.71	0.00
	B - Quarry	0.00	0.00	0.00	2.17
	C - L3603 (W)	3.95	0.00	0.00	0.00
	D - Processing Facility	0.00	2.14	0.00	0.00

Demand (Veh/TS)

17:00 - 18:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	15.75	0.00
	B - Quarry	0.00	0.00	0.00	2.60
	C - L3603 (W)	14.52	0.00	0.00	0.00
	D - Processing Facility	0.00	0.74	0.00	0.00

18:00 - 19:00

Demand (Veh/TS)

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0.00	0.00	11.98	0.00
	B - Quarry	0.00	0.00	0.00	0.74
	C - L3603 (W)	6.37	0.00	0.00	0.00
	D - Processing Facility	0.00	1.55	0.00	0.00

Vehicle Mix

Heavy Vehicle Percentages

07:00 - 08:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	8	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	6	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

08:00 - 09:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	35	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	4	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

09:00 - 10:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	26	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	7	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

10:00 - 11:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	18	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

11:00 - 12:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	5	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	9	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

12:00 - 13:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	6	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	13	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

13:00 - 14:00

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	20	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	3	0	0	0
	D - Processing Facility	0	100	0	0

14:00 - 15:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	8	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	30	0	0	0
	D - Processing Facility	0	100	0	0

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	36	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	12	0	0	0
	D - Processing Facility	0	100	0	0

15:00 - 16:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	19	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	6	0	0	0
	D - Processing Facility	0	100	0	0

16:00 - 17:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	5	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	19	0	0	0
	D - Processing Facility	0	100	0	0

17:00 - 18:00

Heavy Vehicle Percentages

	To				
		A - L3603 (E)	B - Quarry	C - L3603 (W)	D - Processing Facility
From	A - L3603 (E)	0	0	21	0
	B - Quarry	0	0	0	100
	C - L3603 (W)	2	0	0	0
	D - Processing Facility	0	100	0	0

18:00 - 19:00

Results

Results Summary for whole modelled period

Stream	Max RFC	Max Delay (s)	Max Queue (Veh)	Max LOS	Average Demand (Veh/TS)	Total Junction Arrivals (Veh)
B-CD	0.01	14.48	0.0	B	1.29	15.50
B-AD	0.01	14.46	0.0	B	1.29	15.50
A-BCD	0.00	0.00	0.0	A	0.00	0.00
A-B					0.00	0.00
A-C					16.27	195.23
D-AB	0.01	15.46	0.0	C	1.35	16.18
D-BC	0.01	15.44	0.0	C	1.35	16.18
C-ABD	0.00	0.00	0.0	A	0.00	0.00
C-D					0.00	0.00
C-A					12.58	150.92

Main Results for each time segment

07:00 - 08:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.36	1.36	252.58	0.005	1.36	0.0	0.0	14.329	B
B-AD	1.36	1.36	252.92	0.005	1.36	0.0	0.0	14.309	B
A-BCD	0.00	0.00	560.92	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.21	11.21			11.21				
D-AB	2.36	2.36	236.91	0.010	2.35	0.0	0.0	15.347	C
D-BC	2.36	2.36	237.50	0.010	2.35	0.0	0.0	15.308	C
C-ABD	0.00	0.00	625.59	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	8.32	8.32			8.32				

08:00 - 09:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.44	1.44	249.99	0.006	1.44	0.0	0.0	14.483	B
B-AD	1.44	1.44	250.35	0.006	1.44	0.0	0.0	14.462	B
A-BCD	0.00	0.00	538.91	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	17.01	17.01			17.01				
D-AB	1.58	1.58	234.43	0.007	1.58	0.0	0.0	15.462	C
D-BC	1.58	1.58	234.82	0.007	1.58	0.0	0.0	15.436	C
C-ABD	0.00	0.00	624.39	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	25.27	25.27			25.27				

09:00 - 10:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.63	1.63	251.04	0.006	1.63	0.0	0.0	14.432	B
B-AD	1.63	1.63	251.45	0.006	1.63	0.0	0.0	14.409	B
A-BCD	0.00	0.00	537.74	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	14.25	14.25			14.25				
D-AB	1.94	1.94	235.44	0.008	1.94	0.0	0.0	15.417	C
D-BC	1.94	1.94	235.92	0.008	1.94	0.0	0.0	15.385	C
C-ABD	0.00	0.00	623.78	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	18.17	18.17			18.17				

10:00 - 11:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.33	1.33	251.56	0.005	1.33	0.0	0.0	14.389	B
B-AD	1.33	1.33	251.89	0.005	1.33	0.0	0.0	14.369	B
A-BCD	0.00	0.00	543.28	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	17.40	17.40			17.40				
D-AB	1.22	1.22	236.56	0.005	1.23	0.0	0.0	15.299	C
D-BC	1.22	1.22	236.87	0.005	1.23	0.0	0.0	15.276	C
C-ABD	0.00	0.00	625.63	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	8.95	8.95			8.95				

11:00 - 12:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.19	1.19	251.66	0.005	1.19	0.0	0.0	14.372	B
B-AD	1.19	1.19	251.96	0.005	1.19	0.0	0.0	14.355	B
A-BCD	0.00	0.00	552.40	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	15.21	15.21			15.21				
D-AB	1.27	1.27	236.16	0.005	1.27	0.0	0.0	15.325	C
D-BC	1.27	1.27	236.48	0.005	1.27	0.0	0.0	15.304	C
C-ABD	0.00	0.00	623.02	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	14.31	14.31			14.31				

12:00 - 13:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.19	1.19	252.14	0.005	1.19	0.0	0.0	14.344	B
B-AD	1.19	1.19	252.44	0.005	1.19	0.0	0.0	14.327	B
A-BCD	0.00	0.00	557.41	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	12.34	12.34			12.34				
D-AB	0.95	0.95	236.65	0.004	0.95	0.0	0.0	15.275	C
D-BC	0.95	0.95	236.89	0.004	0.95	0.0	0.0	15.256	C
C-ABD	0.00	0.00	618.99	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	12.15	12.15			12.15				

13:00 - 14:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.66	1.66	250.46	0.007	1.66	0.0	0.0	14.468	B
B-AD	1.66	1.66	250.88	0.007	1.66	0.0	0.0	14.444	B
A-BCD	0.00	0.00	551.32	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	23.36	23.36			23.36				
D-AB	1.55	1.55	235.74	0.007	1.55	0.0	0.0	15.371	C
D-BC	1.55	1.55	236.13	0.007	1.55	0.0	0.0	15.345	C
C-ABD	0.00	0.00	620.79	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	11.03	11.03			11.03				

14:00 - 15:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.77	1.77	251.40	0.007	1.77	0.0	0.0	14.420	B
B-AD	1.77	1.77	251.84	0.007	1.77	0.0	0.0	14.394	B
A-BCD	0.00	0.00	553.73	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	13.57	13.57			13.57				
D-AB	1.72	1.72	235.74	0.007	1.72	0.0	0.0	15.382	C
D-BC	1.72	1.72	236.17	0.007	1.72	0.0	0.0	15.353	C
C-ABD	0.00	0.00	606.36	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	14.79	14.79			14.79				

15:00 - 16:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.16	1.16	251.00	0.005	1.16	0.0	0.0	14.411	B
B-AD	1.16	1.16	251.29	0.005	1.16	0.0	0.0	14.391	B
A-BCD	0.00	0.00	538.89	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	16.44	16.44			16.44				
D-AB	1.38	1.38	235.81	0.006	1.38	0.0	0.0	15.358	C
D-BC	1.38	1.38	236.15	0.006	1.38	0.0	0.0	15.336	C
C-ABD	0.00	0.00	609.22	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	13.09	13.09			13.09				

16:00 - 17:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.09	1.09	250.67	0.004	1.09	0.0	0.0	14.426	B
B-AD	1.09	1.09	250.94	0.004	1.09	0.0	0.0	14.410	B
A-BCD	0.00	0.00	543.75	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	26.71	26.71			26.71				
D-AB	1.07	1.07	236.37	0.005	1.07	0.0	0.0	15.301	C
D-BC	1.07	1.07	236.64	0.005	1.07	0.0	0.0	15.283	C
C-ABD	0.00	0.00	613.96	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	3.95	3.95			3.95				

17:00 - 18:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	1.30	1.30	251.45	0.005	1.30	0.0	0.0	14.390	B
B-AD	1.30	1.30	251.77	0.005	1.30	0.0	0.0	14.371	B
A-BCD	0.00	0.00	551.58	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	15.75	15.75			15.75				
D-AB	0.37	0.37	236.17	0.002	0.37	0.0	0.0	15.269	C
D-BC	0.37	0.37	236.27	0.002	0.37	0.0	0.0	15.263	C
C-ABD	0.00	0.00	611.52	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	14.52	14.52			14.52				

18:00 - 19:00

Stream	Total Demand (Veh/TS)	Junction Arrivals (Veh)	Capacity (Veh/TS)	RFC	Throughput (Veh/TS)	Start queue (Veh)	End queue (Veh)	Delay (s)	Unsignalised level of service
B-CD	0.37	0.37	252.72	0.001	0.38	0.0	0.0	14.268	B
B-AD	0.37	0.37	252.81	0.001	0.38	0.0	0.0	14.262	B
A-BCD	0.00	0.00	549.08	0.000	0.00	0.0	0.0	0.000	A
A-B	0.00	0.00			0.00				
A-C	11.98	11.98			11.98				
D-AB	0.78	0.78	237.40	0.003	0.77	0.0	0.0	15.213	C
D-BC	0.78	0.78	237.59	0.003	0.77	0.0	0.0	15.200	C
C-ABD	0.00	0.00	620.96	0.000	0.00	0.0	0.0	0.000	A
C-D	0.00	0.00			0.00				
C-A	6.37	6.37			6.37				